

KRT2024-01 Amendment 3

Neal Heary with Thoroughbred Construction Group asked-

“Can you confirm:

- walk pads are required / walk pad locations
- membrane is being secured to walls with termination bar and covered with 24 gauge counterflashing “

KRT response-

“Walk pads are only required per the manufacturer’s requirements to meet the 20 year warranty specifications. Otherwise, they may be listed as optional in the bid surrounding any work areas on the roof.

Yes, the membrane will be secured to the walls with termination bar and covered with 24 gauge counterflashing. The existing stone caps will remain.”